SECTION J – ATTACHMENT 0001

PERFORMANCE WORK STATEMENT (PWS)

BASE OPERATIONS SUPPORT (BOS) SERVICES

U.S. ARMY GARRISON FORT BRANNOCK, WISCONSIN

Directorate of Public Works (DPW)

Solicitation No. W9131B-27-R-0006

Version 1.0 – 16 November 2026

Common Levels of Support (CLS) in this PWS: 402 Custodial Services; 403 Refuse Removal and Recycling; 404 Maintenance – Grounds; 408 Snow, Ice and Sand Removal; 420 Facility Maintenance (Demand Maintenance Orders); 510 Pest Management.

Technical Exhibits: TE 1 through TE 10 are bound at the end of this attachment. TE 11 (Installation Maps) is provided electronically in the solicitation technical library.

Prepared by: Directorate of Public Works, Business Operations and Integration Division, Fort Brannock, WI 54409. **Contracting activity:** Mission and Installation Contracting Command (MICC) – Fort Brannock.

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited. This PWS is part of the solicitation package and is subject to change by solicitation amendment.

TABLE OF CONTENTS

PART 1 – GENERAL INFORMATION

1.1 General · 1.2 Background · 1.3 Scope – Common Levels of Support · 1.4 Period of Performance

1.5 Place of Performance and Hours of Operation · 1.6 Recognized Holidays · 1.7 Climatic Conditions

1.8 Quality Control · 1.9 Quality Assurance · 1.10 Key Personnel · 1.11 Security Requirements

1.12 Phase-In and Phase-Out · 1.13 Contractor Manpower Reporting · 1.14 Workload Changes · 1.15 Safety and Environmental

1.16 Mission-Essential Services · 1.17 Contractor Employee Conduct · 1.18 Organizational Conflict of Interest · 1.19 Service Contract Labor Standards · 1.20 Invoicing

PART 2 – DEFINITIONS AND ACRONYMS

PART 3 – GOVERNMENT-FURNISHED PROPERTY, FACILITIES AND SERVICES

PART 4 – CONTRACTOR-FURNISHED ITEMS AND SERVICES

PART 5 – SPECIFIC TASKS

5.1 CLS 402 – Custodial Services

5.2 CLS 403 – Refuse Removal and Recycling

5.3 CLS 404 – Maintenance – Grounds

5.4 CLS 408 – Snow, Ice and Sand Removal

5.5 CLS 510 – Pest Management

5.6 CLS 420 – Facility Maintenance (Demand Maintenance Orders)

5.7 Meetings and Recurring Reports

PART 6 – APPLICABLE PUBLICATIONS

PART 7 – ATTACHMENT / TECHNICAL EXHIBIT LISTING

TE 1 – Performance Requirements Summary

TE 2 – Deliverables Schedule

TE 3 – Estimated Workload Summary

TE 4 – Custodial Cleaning Standards and Frequencies

TE 5 – Custodial Facility List (Part A – Facilities Serviced; Part B – Optional Facilities)

TE 6 – Grounds Maintenance Areas

TE 7 – Refuse Collection Workload

TE 8 – Snow and Ice Removal Areas and Priorities

TE 9 – Pest Management Workload

TE 10 – Historical Workload Data

TE 11 – Installation Maps (electronic only; not bound)

Note: Paragraph numbers in this PWS are referenced by the Performance Requirements Summary (TE 1), the Deliverables Schedule (TE 2) and Section B. Where a Technical Exhibit and the text of Parts 1–5 conflict, the text governs, except that the facilities, areas and quantities to be serviced are those stated in the Technical Exhibits.

PART 1 – GENERAL INFORMATION

1.1 General. This is a non-personal services contract to provide Base Operations Support (BOS) services for the U.S. Army Garrison (USAG) Fort Brannock, Wisconsin. The Government will not exercise any supervision or control over the contract service providers performing the services herein. Such contract service providers shall be accountable solely to the Contractor who, in turn, is responsible to the Government.

1.1.1 Description of Services. The Contractor shall provide all personnel, equipment, supplies, facilities, transportation, tools, materials, supervision, and other items and non-personal services necessary to perform the Common Levels of Support (CLS) functions listed in paragraph 1.3 as defined in this Performance Work Statement (PWS), except for those items specified as Government-furnished property and services in Part 3. The Contractor shall perform to the standards in this contract.

1.1.2 Objectives. The Government's objectives are clean, safe and sanitary facilities; well-kept grounds that present a professional military appearance; timely collection of refuse and recyclables; safe passage on installation roads, parking areas and walks during the winter season; protection of people, facilities and stored products from pests; and responsive minor maintenance of real property. The intent is to establish work requirements that are performance-based and results-oriented, allowing the Contractor to determine the most cost-effective way to meet the standards, emphasizing innovation and commercial best practices.

1.2 Background. Fort Brannock is located in Langlade County in north-central Wisconsin, approximately nine miles northwest of Antigo. The installation was established in 1939 as a National Guard summer training camp, was federalized in 1940, and today supports Active and Reserve Component training, the Regional NCO Academy and Brannock Army Airfield (AAF). The installation comprises approximately 14,860 acres. About 1,240 acres make up the cantonment area and the airfield; the remaining acreage consists of ranges and maneuver training areas managed by the Directorate of Plans, Training, Mobilization and Security (DPTMS). The real property inventory includes 418 buildings with approximately 3.1 million square feet of floor area. The daily population is approximately 4,300 military, civilian and contractor personnel, rising to as many as 6,500 during Reserve Component annual training from June through August.

1.2.1 Facilities and Areas in Scope. Not every installation facility is serviced under this contract. The facilities, areas and quantities to be serviced under each CLS are identified in the Technical Exhibits (TE) listed in Part 7. Family housing (privatized under the Residential Communities Initiative), the Army Health Clinic (Bldg 1100, U.S. Army Medical Command), the Commissary (Bldg 1600, Defense Commissary Agency), the Dining Facility (Bldg 1310, serviced under the installation food service contract) and the Brannock Club (Bldg 1550, Nonappropriated Fund) are not serviced under CLS 402 Custodial Services. Some of these facilities are included in the refuse, snow removal and pest management workload where they are listed in TE 7, TE 8 and TE 9.

1.2.2 Current Contract. These services are currently performed under a BOS contract that expires 30 June 2027. Historical contract and workload information is provided in TE 10 for information only. Historical workload is not a guarantee of future workload.

1.3 Scope – Common Levels of Support. The Contractor shall perform the CLS functions in Table 1-1 IAW the paragraphs and Technical Exhibits shown. Contract line item numbers (CLINs) are shown for the base period; option period CLINs are numbered 1001–1010, 2001–2010, 3001–3010 and 4001–4010.

Table 1-1. Common Levels of Support and Contract Line Items

CLS	Service Title	PWS Section	Technical Exhibit(s)	CLIN (Base Period)	Pricing Basis
—	Phase-in	1.12	—	0001	Firm-fixed price (FFP)
402	Custodial Services	5.1	TE 4, TE 5 Part A	0002	FFP, per CSF per month
403	Refuse Removal and Recycling	5.2	TE 7	0003	FFP
404	Maintenance – Grounds	5.3	TE 6	0004	FFP
408	Snow, Ice and Sand Removal (first 14 snow events per season)	5.4	TE 8	0005	FFP
420	Facility Maintenance – Demand Maintenance Orders	5.6	TE 10	0006	FFP (labor); cost-reimbursable material
510	Pest Management	5.5	TE 9	0007	FFP
408	Additional snow events (above 14 per season)	5.4.7	TE 8	0008	Fixed unit price per event
402	Special and emergency cleaning	5.1.10	TE 10	0009	Fixed unit price per request
402	Optional facilities (TE 5 Part B) – OPTIONAL	5.1.12	TE 5 Part B	0010	FFP, per CSF per month

1.4 Period of Performance. The period of performance consists of a 30-day phase-in period (1 June 2027 through 30 June 2027), a 12-month base period (1 July 2027 through 30 June 2028) and four 12-month option periods: Option Period 1, 1 July 2028 through 30 June 2029; Option Period 2, 1 July 2029 through 30 June 2030; Option Period 3, 1 July 2030 through 30 June 2031; and Option Period 4, 1 July 2031 through 30 June 2032. If all options are exercised, the total period of performance, excluding phase-in, is five (5) years.

1.5 Place of Performance and Hours of Operation.

1.5.1 Place of Performance. Work shall be performed on the Fort Brannock main cantonment, Brannock AAF, the Range Complex (Range Control, Ranges 12 and 18) and the Ammunition Supply Point (ASP). Maps of these areas are provided in TE 11.

1.5.2 Hours of Operation. Normal installation duty hours are 0730 to 1630, Monday through Friday, excluding Federal holidays. The Contractor shall maintain an adequate workforce for the uninterrupted performance of all tasks defined within this PWS. Custodial services in occupied administrative facilities shall be performed between 1700 and 0600 unless otherwise approved by the Contracting Officer's Representative (COR). Child, Youth and School Services (CYS) facilities shall be cleaned after the facility closes (1830) and completed before 0500. Grounds maintenance shall be performed between 0700 and 1700 Monday through Friday, except that mowing adjacent to CYS facilities and barracks shall not begin before 0800. Snow and ice removal is performed 24 hours a day, 7 days a week during snow events (5.4).

1.5.3 DPW Work Reception. The Government operates the DPW Work Reception desk (Bldg 1002) from 0700 to 1630, Monday through Friday. After hours, emergency calls are routed to the Installation Operations Center. The Contractor shall provide a telephone number staffed 24 hours a day, 7 days a week for emergency Demand Maintenance Orders (DMOs), pest emergencies and snow call-outs.

1.6 Recognized Holidays. The Contractor is not required to perform services on the following Federal holidays, except in facilities assigned a 7W frequency in TE 5, for emergency DMOs, and for snow and ice removal: New Year's Day, Martin Luther King Jr.'s Birthday, Washington's Birthday, Memorial Day, Juneteenth National Independence Day, Independence Day, Labor Day, Columbus Day, Veterans Day, Thanksgiving Day and Christmas Day. Holidays falling on a weekend are observed as directed by the Federal calendar (5 U.S.C. 6103). Services missed on a holiday shall be performed on the next service day unless the COR waives them.

1.7 Climatic Conditions. Fort Brannock has a humid continental climate with long, cold winters. Average annual precipitation is approximately 32 inches. The 30-year normal annual snowfall is 64 inches, with measurable snow expected from late October through April. The January mean temperature is 12 °F with recorded extremes of –35 °F; the July mean is 69 °F. Frost penetration commonly exceeds 48 inches. The average frost-free period is about 120 days, from mid-May to mid-September. For this contract the mowing season is 1 May through 15 October (24 weeks) and the snow season is 15 October through 30 April.

1.8 Quality Control. The Contractor shall develop and maintain an effective quality control program to ensure services are performed IAW this PWS. The Contractor shall develop and implement procedures to identify, prevent and ensure

non-recurrence of defective services. The Contractor's Quality Control Plan (QCP) (CDRL A002) shall describe the inspection system for each CLS, including the frequency of inspections, the names and qualifications of inspectors, and the method of documenting and correcting deficiencies. A copy of each completed inspection report shall be provided to the COR by the 5th business day of the following month.

1.9 Quality Assurance. The Government will evaluate the Contractor's performance under this contract using the methods of surveillance in the Quality Assurance Surveillance Plan (QASP), including random sampling, periodic inspection, 100 percent inspection of selected outputs, and validated customer complaints. The Performance Requirements Summary (TE 1) states the performance objectives, the performance thresholds (Acceptable Quality Levels, AQLs) and the remedies the Government may apply.

1.10 Key Personnel. The following positions are key personnel: Project Manager; Alternate Project Manager; Custodial Manager; Grounds and Snow Removal Supervisor; and Pest Management Supervisor. The Project Manager or Alternate shall be available on the installation during normal duty hours and reachable by telephone within 30 minutes at all other times. The Pest Management Supervisor shall hold current Wisconsin Department of Agriculture, Trade and Consumer Protection (DATCP) commercial applicator certification in the categories required for turf and ornamental and structural pest control, and shall obtain DoD certification under DoDI 4150.07 within one year of contract start. Resumes for key personnel are due with the proposal and for any replacement not later than 10 business days before the change (CDRL A003).

1.11 Security Requirements. All Contractor employees requiring access to the installation shall be vetted through the Defense Biometric Identification System (DBIDS) and shall complete Antiterrorism Level I awareness training within 30 calendar days of contract start or of the employee's start of work, and annually thereafter. Employees shall complete iWATCH Army and Operations Security (OPSEC) awareness training within 30 days of start. Contractor employees working in CYS facilities shall complete the background checks required by AR 608-10 and DoDI 1402.05 before working unescorted in those facilities. The Contractor shall establish a key control program; lost keys shall be reported to the COR within four hours of discovery. The cost of re-keying or core replacement caused by lost Contractor-issued keys will be deducted from the Contractor's invoice.

1.12 Phase-In and Phase-Out. During the 30-day phase-in period (CLIN 0001) the Contractor shall hire and train its workforce, obtain installation access, complete the joint inventory of Government-furnished property (Part 3), and observe the incumbent's operations. The Phase-In Plan (CDRL A001) is due 10 business days after contract award. On the first day of the base period the Contractor shall provide a fully qualified workforce capable of performing all work required under this contract. During the 30 days before contract completion the Contractor shall cooperate fully with any successor contractor and shall not defer required work for the purpose of transferring responsibility to the successor.

1.13 Contractor Manpower Reporting. The Contractor shall report ALL Contractor labor hours (including subcontractor labor hours) required for performance of services provided under this contract via the Enterprise Contractor Manpower Reporting Application (ECMRA) in SAM.gov. The reporting period is the period of performance not to exceed 12 months ending September 30 of each Government fiscal year, and the data must be reported by October 31 of each calendar year (CDRL A010).

1.14 Workload Changes. The Government reserves the right to add, delete or suspend facilities and areas listed in the Technical Exhibits when facilities are constructed, renovated, closed, vacated or demolished. The Contracting Officer will issue a written modification identifying the facility, the CSF or area added or deleted, and the effective date. Adjustments to CLIN 0002 will be computed as the CSF added or deleted multiplied by the contract unit price per CSF per month. Adjustments to grounds areas will be computed using the unit prices per acre or square foot in Section B. Cumulative changes within plus or minus 10 percent of the TE 5 Part A CSF will be made at the contract unit prices; changes beyond 10 percent may be negotiated. Suspensions of 30 calendar days or longer will be credited at the same rates.

1.15 Safety and Environmental. The Contractor shall comply with 29 CFR 1910 and 1926, EM 385-1-1 and installation safety requirements. The Contractor shall provide a verbal report of any accident involving injury, death or damage to Government property to the COR within one hour, and a written report within five business days (CDRL A009). The Contractor shall comply with the installation Environmental Management System, the Spill Prevention, Control and

Countermeasure Plan and the Integrated Pest Management Plan, and shall immediately report any spill of petroleum, pesticide or other hazardous material to the Fort Brannock Fire Department (911) and the DPW Environmental Division.

1.16 Mission-Essential Services. Priority 1 snow and ice removal (5.4.3), emergency DMOs (5.6.2), emergency cleaning (5.1.10) and custodial services in facilities with a 7W frequency are mission-essential services under DFARS 252.237-7023. The Contractor's Mission-Essential Contractor Services Plan, submitted with the proposal, shall describe how these services will continue during a crisis, pandemic or installation emergency, including alternate staffing and the time required to restore full service.

1.17 Contractor Employee Conduct. The Contractor shall ensure its employees present a neat appearance, are easily recognized as Contractor personnel, and comply with installation rules on traffic, smoking, firearms and the use of Government telephones and computers. The Contracting Officer may require the Contractor to remove from the installation any employee who endangers persons or property, whose continued employment is inconsistent with the interest of military security, or whose conduct is otherwise unacceptable.

1.18 Organizational Conflict of Interest. Contractor and subcontractor personnel performing work under this contract may receive, have access to, or participate in the development of proprietary or source selection information, or may perform evaluation services that create a current or subsequent organizational conflict of interest as defined in FAR Subpart 9.5. The Contractor shall notify the Contracting Officer immediately whenever it becomes aware that such access or participation may create an actual or potential conflict.

1.19 Service Contract Labor Standards. This contract is subject to the Service Contract Labor Standards (41 U.S.C. chapter 67). The applicable Department of Labor wage determination for Langlade County, Wisconsin, is incorporated in Section J. Snow removal equipment operators who also perform grounds maintenance shall be paid the rate for the classification of the work performed in each hour.

1.20 Invoicing. The Contractor shall submit one invoice per month through the Procurement Integrated Enterprise Environment (PIEE) Wide Area WorkFlow, itemized by CLIN. Invoices for CLIN 0002 shall show the CSF serviced for the month and any credits for suspended areas; invoices for CLINs 0008 and 0009 shall list each snow event or special cleaning request with the date and the COR's acceptance.

PART 2 – DEFINITIONS AND ACRONYMS

2.1 Definitions.

2.1.1 Acceptable Quality Level (AQL). The maximum allowable deviation from a performance standard before a remedy is applied (TE 1).

2.1.2 Capability Level. The level of custodial service assigned to a facility in TE 5. *Capability I – Enhanced Service* applies to CYS facilities and requires a sanitized environment suitable for infants and children. *Capability II – Standard Service* applies to physical fitness and recreation facilities with locker rooms, showers and high traffic. *Capability III – Basic Service* applies to administrative, training, maintenance, warehouse and other facilities. Task frequencies for each level are in TE 4.

2.1.3 Cleanable Square Feet (CSF). The floor area of a facility to be serviced, as shown in TE 5, column 12. CSF is the sum of restroom, carpeted and hard floor areas to be serviced and is the basis for payment under CLIN 0002 and for workload adjustments under 1.14.

2.1.4 Gross Square Feet (GSF). The total area of all floors of a facility measured to the outside face of the exterior walls, as recorded in the Army real property inventory. GSF is shown in TE 5 for information.

2.1.5 Contracting Officer's Representative (COR). An individual designated in writing by the Contracting Officer to perform specific technical or administrative functions. The COR has no authority to make any commitments or changes that affect price, quality, quantity, delivery or other terms and conditions of the contract.

2.1.6 Demand Maintenance Order (DMO). A request for minor maintenance or repair of real property that is not scheduled, requiring not more than 16 labor hours and not more than $2,500 in material per order (5.6). DMOs are classified as Emergency (Priority 1), Urgent (Priority 2) or Routine (Priority 3).

2.1.7 Defect. A failure to meet a performance standard in TE 1 that is observed by the Government and validated by the COR.

2.1.8 Facility Number (FAC NO). The real property building or facility number assigned by the DPW Real Property Office. Facility numbers may include an alphabetic suffix for separate buildings sharing a base number (for example, 2104A and 2104B).

2.1.9 Facility Service Frequency. The number of days per week (or per month) on which routine custodial service is performed at a facility, shown in TE 5, column 13:

Code	Definition	Service days
7W	Seven days per week, Monday through Sunday, including Federal holidays.	7 per week
6W	Six days per week, Monday through Saturday, excluding Federal holidays.	6 per week
5W	Five days per week, Monday through Friday, excluding Federal holidays.	5 per week
3W	Three days per week, Monday, Wednesday and Friday (or as scheduled with the COR), excluding Federal holidays.	3 per week
2W	Twice weekly, such as Monday and Thursday or Tuesday and Friday.	2 per week
W	Weekly; 52 times during each 12-month period at intervals of six to eight calendar days.	1 per week
M	Monthly; 12 times during each 12-month period at intervals of 28 to 31 calendar days.	1 per month

2.1.10 Task Frequency. The frequency at which an individual cleaning task is performed (TE 4). "1X daily" and "2X daily" mean once or twice on each service day of the facility. Weekly, monthly, quarterly (four times per 12 months at intervals of 80 to 100 days), semiannual (twice per 12 months at intervals of 160 to 200 days) and annual (once per 12 months at intervals of 335 to 395 days) tasks are performed regardless of the facility service frequency.

2.1.11 Improved Grounds. Developed areas with lawns and landscape plantings that receive intensive maintenance, such as areas around administrative, community, CYS and barracks facilities, parade and ceremonial areas, gates and primary road medians. Improved turf is maintained between 2½ and 4 inches.

2.1.12 Semi-Improved Grounds. Areas maintained to a lesser degree than improved grounds, such as industrial areas, airfield infields and clear zones, road shoulders, and outlying or low-visibility locations, where vegetation is controlled for operational, safety, fire-prevention or appearance reasons. Semi-improved turf is maintained between 4 and 10 inches, except airfield areas (5.3.3).

2.1.13 Unimproved Grounds. All other grounds, such as firebreaks, fence lines and drainage areas, where vegetation is controlled once or twice per season to prevent encroachment, maintain access and reduce fire hazard.

2.1.14 Mowing Cycle. One complete mowing, including trimming, of all areas in a grounds area.

2.1.15 Snow Event. A period of snowfall producing an accumulation of 2 inches or more, measured at the DPW weather station at Bldg 2310, or any freezing rain or ice accumulation for which the COR directs treatment of Priority 1 routes. Snowfall that continues after a break of less than 12 hours is part of the same event. Drifting that requires plowing of Priority 1 or 2 routes with no new snowfall is a separate event only when directed by the COR.

2.1.16 Lane-Mile. One mile of a single 12-foot traffic lane. A two-lane road one mile long is two lane-miles.

2.1.17 Container Lift / Roll-off Pull. One emptying of a front-load container into a collection vehicle, or one removal of a roll-off container to a disposal or recycling facility and its return.

2.1.18 Integrated Pest Management (IPM). A sustainable approach to managing pests that combines biological, cultural, physical and chemical tools in a way that minimizes health, environmental and economic risks, as described in DoDI 4150.07 and the Fort Brannock Integrated Pest Management Plan (IPMP).

2.2 Acronyms.

Acronym	Meaning	Acronym	Meaning
AAF	Army Airfield	ECMRA	Enterprise Contractor Manpower Reporting Application
AQL	Acceptable Quality Level	FFP	Firm-Fixed Price
ASP	Ammunition Supply Point	GFE / GFF / GFP	Government-Furnished Equipment / Facilities / Property
BASH	Bird/Wildlife Aircraft Strike Hazard	GSF	Gross Square Feet
BOD	Beneficial Occupancy Date	IPMC	Installation Pest Management Coordinator
BOS	Base Operations Support	LM	Lane-Mile
CATCD	Facility Category Code (DA Pam 415-28)	LRC	Logistics Readiness Center
CDRL	Contract Data Requirements List	MSW / OCC / CMR	Municipal Solid Waste / Old Corrugated Cardboard / Commingled Recyclables
CIF	Central Issue Facility	NAF	Nonappropriated Fund
CLIN	Contract Line Item Number	NCOA	Noncommissioned Officer Academy
CLS	Common Levels of Support	NEC	Network Enterprise Center
COR	Contracting Officer's Representative	PRS	Performance Requirements Summary
CSF	Cleanable Square Feet	QASP / QCP	Quality Assurance Surveillance Plan / Quality Control Plan
CY	Cubic Yard	RCI	Residential Communities Initiative
CYS	Child, Youth and School Services	RPLANS	Real Property Planning and Analysis System
DES	Directorate of Emergency Services	RSO	Religious Support Office
DFMWR	Directorate of Family and Morale, Welfare and Recreation	SF / SY / LF	Square Feet / Square Yards / Linear Feet
DHR	Directorate of Human Resources	TE	Technical Exhibit
DMO	Demand Maintenance Order	TEMF	Tactical Equipment Maintenance Facility
DPTMS	Directorate of Plans, Training, Mobilization and Security	UH / UPH	Unaccompanied Housing / Unaccompanied Personnel Housing
DPW	Directorate of Public Works	VCC	Visitor Control Center

PART 3 – GOVERNMENT-FURNISHED PROPERTY, FACILITIES AND SERVICES

3.1 General. The Government will provide, without cost to the Contractor, the facilities, equipment, materials and services listed in this Part. Government-furnished property (GFP) shall be used only in performance of this contract. An initial joint inventory of GFP shall be conducted by the Contractor and the COR on or before the first day of the base period IAW DA Pam 710-2-1 and recorded on DA Form 2062, Hand Receipt.

3.2 Government-Furnished Facilities (GFF). The Government will provide the facilities in Table 3-1 for the Contractor's administrative offices, shops, storage and vehicle parking.

Table 3-1. Government-Furnished Facilities

Bldg No.	Facility	GSF	Contractor Use
2410	BOS Contractor Administration Building	7,200	Project management office, quality control, work reception, training room
2412	Shops and Storage Building	12,800	Grounds equipment maintenance, custodial supply storage, pest management shop
2414	Covered Vehicle and Equipment Storage (pole building)	4,000	Snow removal and mowing equipment storage
2416	Salt and Sand Storage Dome	6,360	Government deicing material stockpile (1,200-ton capacity) (4.5)

3.2.1 The Contractor shall keep GFF clean, orderly and free of pests and fire hazards, and shall perform custodial services in GFF at no additional cost to the Government. GFF is not included in TE 5 and shall not be invoiced under CLIN 0002. Pesticides shall be stored only in the pest management shop in Bldg 2412.

3.3 Government-Furnished Equipment (GFE). The Government will provide the equipment in Table 3-2. The Contractor shall perform operator maintenance and scheduled services on GFE IAW the manufacturer's instructions. Repairs to GFE caused by Contractor negligence or abuse are at the Contractor's expense.

Table 3-2. Government-Furnished Equipment

Item	Description	Qty	Remarks
1	Dump truck, 10-wheel, with 11-ft reversible plow, wing and 10-CY spreader	4	Model years 2016–2021
2	Wheel loader, 3-CY bucket, with 14-ft snow pusher	2	
3	Compact tractor with 60-in. broom and 54-in. snow blower (sidewalk unit)	3	
4	Zero-turn mower, 72-in. deck	6	Replacement by Contractor after FY29 (Part 4)
5	Wide-area rotary mower, 16-ft	2	
6	Tractor, 85 hp, with 15-ft batwing rotary cutter	1	Semi-improved and unimproved areas
7	Pest management vehicle with locking chemical compartment and spill kit	1	

3.4 Utilities. The Government will furnish electricity, water, sewer, heat and natural gas for GFF and for the performance of work in Government facilities. The Contractor shall conserve utilities and shall turn off lights and close windows and doors in facilities after cleaning.

3.5 Government-Furnished Services. The Government will provide installation fire and emergency medical response, police services, and access to the installation telephone system and the GFEBS work management system for DMO processing (5.6.4). Government computers and network accounts will be provided for up to six Contractor personnel.

PART 4 – CONTRACTOR-FURNISHED ITEMS AND SERVICES

4.1 General. Except for the items specifically stated as Government-furnished in Part 3, the Contractor shall furnish everything required to perform this PWS.

4.2 Custodial Supplies and Equipment. The Contractor shall furnish all custodial equipment, cleaning chemicals, floor finishes, and consumable supplies, including toilet tissue, paper towels, hand soap, seat covers, feminine hygiene product bags and trash can liners, for all TE 5 Part A facilities. Products shall meet the recycled-content and environmentally preferable purchasing requirements of FAR Subpart 23.1. Vacuum cleaners shall be certified under the Carpet and Rug

Institute Seal of Approval program. Dispensers installed by the Government shall be used; the Contractor shall not install proprietary dispensers without COR approval.

4.3 Refuse Containers and Vehicles. The Contractor shall furnish all front-load and roll-off containers, collection vehicles and disposal or recycling facility access required by 5.2 and TE 7, including tipping fees.

4.4 Pesticides. The Contractor shall furnish all pesticides, baits, traps and application equipment. Only EPA-registered pesticides approved by the Installation Pest Management Coordinator (IPMC) and listed in the IPMP may be used. Safety Data Sheets shall be maintained on site.

4.5 Deicing Materials. The Government will furnish rock salt and sand from the stockpile at Facility 2416. The Contractor shall load, transport and apply the material and shall furnish any liquid anti-icing material and sidewalk ice-melt (calcium magnesium acetate or equivalent approved by the COR) used at building entrances.

4.6 Vehicles and Uniforms. Contractor vehicles shall display the company name. Contractor employees shall wear a uniform or other distinctive clothing and an identification badge that clearly identifies them as Contractor personnel.

PART 5 – SPECIFIC TASKS

5.1 CLS 402 – CUSTODIAL SERVICES

5.1.1 General. The Contractor shall provide custodial services in the facilities listed in TE 5, Part A, at the capability level and facility service frequency shown for each facility, to the standards and task frequencies in TE 4. TE 5, Part A contains 48 facility lines; 47 facilities are serviced, with a total of 557,560 CSF (1,060,920 GSF). Services are required only in the cleanable areas defined in Note 2 to TE 5. Facilities and areas not listed in TE 5, Part A are not part of the base requirement.

5.1.2 Capability Levels. TE 5 groups facilities by capability level: Capability I – Enhanced Service, 5 facilities (92,270 CSF); Capability II – Standard Service, 6 facilities (96,370 CSF); and Capability III – Basic Service, 36 facilities (368,920 CSF). The Contractor shall perform each task at the frequency shown in TE 4 for the facility's capability level.

5.1.3 Service Schedule. The Contractor shall submit a cleaning schedule for each facility with its proposal and a monthly schedule to the COR by the 25th day of the preceding month (CDRL A005). Facilities with a 7W frequency (fitness centers, indoor pool, bowling center, military police station, fire station, Visitor Control Center and airfield operations building) shall be serviced every day, including holidays; services in 24-hour facilities shall be coordinated with the building manager to avoid disrupting operations. Services in the Outdoor Pool Bathhouse (Bldg 1532) are seasonal (TE 5, Note 6).

5.1.4 Restrooms, Locker Rooms and Showers. The Contractor shall clean and disinfect all surfaces of toilets, urinals, lavatories, showers, partitions, mirrors, dispensers and drinking fountains, and shall restock all dispensers so that supplies do not run out between services. Restrooms identified by Note 3 in TE 5 shall be serviced twice on each service day, with one service during the facility's operating hours. Floor drains shall be flushed weekly to prevent odors.

5.1.5 Trash and Recycling. The Contractor shall empty all trash and recycling receptacles, replace liners, and transport trash and recyclables to the nearest container listed in TE 7. Cardboard shall be broken down and placed in OCC containers where provided. Shredded paper and classified waste are removed by the occupant and are excluded.

5.1.6 Unaccompanied Personnel Housing (Barracks). In UPH barracks Bldgs 1402, 1403 and 1404 the Contractor shall service only the common areas: entry lobbies, dayrooms, laundry rooms, corridors, stairwells and common latrines (TE 5, Note 5). Soldier living modules, the unit supply rooms and the arms rooms are excluded. Barracks Bldg 1407 is vacant (TE 5, Note 4) and shall not be serviced. When the barracks are occupied by Reserve Component units during annual training (June through August), the COR may direct up to two additional services per week in the common latrines of Bldgs 1402–1404, which will be ordered under CLIN 0009.

5.1.7 Periodic Floor Care. The Contractor shall spray buff, strip and refinish resilient floors and extract carpets at the frequencies in TE 4. Strip-and-refinish and carpet extraction shall be scheduled in advance with the COR and building manager and performed when the area is unoccupied, preferably on weekends. Capability III facilities contain approximately 177,650 SF of carpet, which shall be hot-water extracted once each year. Floor care shall not be performed in CYS facilities within 12 hours before the facility opens.

5.1.8 Windows and Glass. The Contractor shall clean entrance glass and interior glass at the frequencies in TE 4 and shall clean both sides of exterior windows up to 12 feet above grade twice each year in Capability I and II facilities and once each year in Capability III facilities, between 15 May and 30 September. Windows above 12 feet are excluded.

5.1.9 Wood Gymnasium Floors. The wood gymnasium floors in Bldg 1520 (14,200 SF) and Bldg 1524 (11,600 SF) are included in the hard floor SF in TE 5 (Note 10). The Contractor shall dust-mop the floors twice on each service day, damp-mop with a cleaner approved by the floor finish manufacturer, and screen and recoat each floor once a year during the annual August maintenance closure of not more than five calendar days. Game-line painting and sanding are excluded.

5.1.10 Special and Emergency Cleaning. The COR may order special cleaning (such as cleaning after a ceremony, change of command or conference) and emergency cleaning (such as clean-up after flooding, sewage back-up or a body-fluid spill). Emergency cleaning shall begin within two hours of notification, 24 hours a day. Special cleaning shall be completed on the date and time stated in the order. Special and emergency cleaning is ordered and priced per request under CLIN 0009. Historical requests are shown in TE 10.

5.1.11 Closures and Unoccupied Areas. When a facility or a portion of a facility is closed for renovation, or is otherwise unoccupied for 30 calendar days or longer, the COR will suspend services in writing and the CSF will be credited under 1.14. Unoccupied areas of a serviced facility shall receive a monthly cleaning (dust, vacuum or sweep, and flush fixtures) unless the COR suspends the area.

5.1.12 Optional Facilities. The facilities in TE 5, Part B – UPH Barracks Bldg 1410 (under construction, beneficial occupancy estimated September 2028) and Child Development Center III, Bldg 3116 (programmed, beneficial occupancy estimated FY29) – are not part of the base requirement. They shall be serviced only after the Contracting Officer exercises Optional CLIN 0010 (or x010 in an option period) by written modification. Part B GSF and CSF are design estimates and will be adjusted to the as-built CSF when the option is exercised.

5.1.13 Facilities Not Serviced. The following are not serviced under CLS 402: the Dining Facility (Bldg 1310), the Army Health Clinic (Bldg 1100) and the Veterinary Treatment Facility (Bldg 1106), the Commissary (Bldg 1600), the Brannock Club (Bldg 1550), family housing, the Government-furnished facilities in Table 3-1, and any facility not listed in TE 5, Part A. Mechanical, electrical and communications rooms, food-preparation areas, vaults and the areas excluded by the notes to TE 5 are not serviced in any facility.

5.2 CLS 403 – REFUSE REMOVAL AND RECYCLING

5.2.1 General. The Contractor shall collect municipal solid waste (MSW), old corrugated cardboard (OCC) and commingled recyclables (CMR) from the containers listed in TE 7 at the frequencies shown, transport the material, and dispose of MSW at a permitted Subtitle D landfill and recyclables at a permitted materials recovery facility selected by the Contractor. TE 7 lists 43 front-load containers requiring an estimated 99 lifts per week, and 4 roll-off containers requiring an estimated 64 pulls per year. The estimated annual quantity is 1,844 tons. All tipping and recycling fees are included in CLIN 0003.

5.2.2 Containers. The Contractor shall furnish, place, maintain and replace all containers. Containers shall be labeled with the waste stream, the Contractor's name and a telephone number, and shall be kept clean, painted, and free of holes and odors. Damaged containers shall be repaired or replaced within two business days of notification. Container sizes and locations shall not be changed without COR approval. Containers serving the Dining Facility (Bldg 1310) shall be steam-cleaned monthly from May through September.

5.2.3 Collection Schedule. Collections shall occur on the days agreed with the COR. Collections near barracks and CYS facilities shall not begin before 0700. Collections at the Dining Facility shall be made six days per week, Monday through Saturday. The area within 10 feet of each container shall be left free of spilled refuse after each lift. Containers at the Range Complex are serviced only from 1 April through 30 November (TE 7, Note 3).

5.2.4 Overflow and Additional Lifts. Containers shall not overflow. The Contractor shall perform additional lifts within 24 hours of a COR request; up to 50 additional lifts per year are included in CLIN 0003.

5.2.5 Reporting. The Contractor shall submit a monthly report of tons collected by waste stream, supported by scale tickets (CDRL A007). The data is used for the Army Solid Waste Annual Report and the installation diversion rate.

5.2.6 Exclusions. Hazardous waste, universal waste, regulated medical waste from the Army Health Clinic and Veterinary Treatment Facility, ammunition residue and range brass, and household waste from family housing (collected by the RCI partner) are excluded.

5.3 CLS 404 – MAINTENANCE – GROUNDS

5.3.1 General. The Contractor shall maintain the improved, semi-improved and unimproved grounds, athletic fields, landscaped beds and paved areas listed in TE 6. TE 6 lists 559.5 acres of improved, semi-improved and unimproved grounds (83.1 acres improved; 173.9 acres semi-improved; 302.5 acres unimproved) and 11.6 acres of athletic fields. Family housing areas and training areas are excluded.

5.3.2 Improved Grounds. The Contractor shall mow improved grounds once each week during the mowing season (24 mowing cycles) and maintain turf between 2½ and 4 inches. Mowing shall include trimming around buildings, trees, signs, fences, headstones and other obstacles. Walks and curbs adjacent to improved grounds (TE 6, Table 6-3) shall be

edged every other week during the mowing season (12 times). Clippings shall be removed from walks, streets and parking areas the same day. Fallen leaves shall be removed from improved grounds and beds by 15 November.

5.3.3 Semi-Improved Grounds. The Contractor shall mow semi-improved grounds at the frequencies in TE 6 to maintain vegetation between 4 and 10 inches. Airfield infields, clear zones and runway shoulders at Brannock AAF shall be maintained between 7 and 14 inches IAW the Brannock AAF BASH Plan, and mowing shall be coordinated with Airfield Operations (Bldg 2602) at least 24 hours in advance. Mowing inside the ASP fence requires an escort (TE 6, Note 4).

5.3.4 Unimproved Grounds. Firebreaks and fence lines shall be mowed or cut once each year after 15 July to protect ground-nesting birds, and vegetation shall be kept at least 3 feet from perimeter fences. Stormwater ponds, drainage channels and retention basins shall be cut twice each year and kept free of woody vegetation and debris that restricts flow.

5.3.5 Athletic Fields. The Contractor shall mow athletic fields twice each week during the mowing season to 2 to 2½ inches, aerate twice each year, and line the fields before each scheduled game or event (estimated 120 linings per season). Infields shall be dragged and leveled before each scheduled game.

5.3.6 Landscaped Beds. The Contractor shall weed shrub and planting beds monthly from May through October, prune shrubs and hedges once each year to maintain their natural form, and apply shredded hardwood mulch to a 3-inch depth once each year by 1 June.

5.3.7 Paved Areas. The Contractor shall police litter and debris from parking lots, sidewalks and walkways weekly during the mowing season and every other week during the rest of the year, and shall sweep parking lots four times each year. Winter sand shall be swept from all parking lots, sidewalks and curb lines by 15 May.

5.3.8 Trees. Tree pruning and removal are performed by DMO (5.6) only. The Contractor shall report hazardous trees to the COR within one business day of discovery and shall remove storm-damaged limbs blocking roads, walks or parking areas within 24 hours.

5.3.9 Fertilizer and Herbicide. Fertilizer and herbicide applications on turf are performed by the Pest Management Supervisor's certified applicators under 5.5.5 and are reported under CDRL A006. The Contractor shall not apply fertilizer within 25 feet of a stormwater pond or channel.

5.4 CLS 408 – SNOW, ICE AND SAND REMOVAL

5.4.1 General. The Contractor shall clear snow and ice from the roads, parking areas, sidewalks and building entrances listed in TE 8, in the priority order shown, IAW the Fort Brannock Snow and Ice Removal Plan. The parking areas and sidewalks in TE 8 are part of the paved areas listed in TE 6, Table 6-3; TE 8 assigns their snow removal priorities.

5.4.2 Start of Operations. Snow removal operations shall begin when accumulation reaches 2 inches, or at the direction of the COR for freezing rain or ice, and shall continue until all Priority 1, 2 and 3 areas are cleared. The Contractor shall have equipment and operators on site within one hour of a call-out at any hour.

5.4.3 Priorities and Response Times. Priority 1 routes and areas (emergency routes, the Main Gate, Army Health Clinic, Military Police Station, Fire Station, Visitor Control Center and Airfield Operations) shall be passable within two hours after operations begin and kept passable throughout the event. Priority 2 areas shall be cleared by 0600 on the next duty day or within six hours after Priority 1 areas are cleared, whichever is later. Priority 3 areas shall be cleared within 24 hours after the end of the snow event. Roads shall be plowed to bare pavement or a compact snow surface treated with salt and sand, curb to curb, without leaving windrows across intersections, driveways or entrances.

5.4.4 Sidewalks and Entrances. Sidewalks, steps, ramps and entrances to Priority 1 facilities and to CYS facilities shall be cleared by 0600 and treated with ice-melt. Other sidewalks shall be cleared within the time allowed for the priority of the adjoining parking area. Seasonal walks at the outdoor pool, outdoor recreation center and athletic fields are not cleared (TE 8, Note 2).

5.4.5 Ice Control. The Contractor shall apply salt and sand from the Government stockpile at Facility 2416 at rates that maintain safe traction, not exceeding 300 pounds of salt per lane-mile per application except as directed by the COR. Salt shall not be applied on the airfield; only airfield-approved deicers furnished by the Government shall be used there.

5.4.6 Snow Storage. Snow shall be pushed or hauled to the snow storage areas shown in TE 11. Snow shall not be piled on shrub beds, against buildings, on fire hydrants, or where it blocks sight lines at intersections. Turf damaged by snow removal shall be repaired by 15 May.

5.4.7 Snow Events Included in the Fixed Price. CLIN 0005 includes up to 14 snow events in each snow season (15 October through 30 April), all ice-control call-outs, and spring sand clean-up (5.3.7). Each event above 14 in a season will be paid at the fixed unit price per event under CLIN 0008. Historical snow events are shown in TE 10.

5.4.8 Snow Event Log. The Contractor shall submit a snow event log within 24 hours after each event showing the start and end times, accumulation, equipment and labor hours used, tons of salt and sand applied, and the time each priority was cleared (CDRL A008).

5.5 CLS 510 – PEST MANAGEMENT

5.5.1 General. The Contractor shall provide integrated pest management services IAW DoDI 4150.07, AR 200-1, Wisconsin Administrative Code chapter ATCP 29, and the Fort Brannock IPMP. All pesticide applications shall be made by, or under the direct supervision of, a certified applicator. The Contractor shall record all pesticide applications on DD Form 1532-1, Pest Management Maintenance Record, and submit a monthly summary to the IPMC (CDRL A006).

5.5.2 Scheduled Structural Services. The Contractor shall inspect and, where pests are found, treat the food-service, CYS, medical and barracks facilities listed in TE 9, Table 9-1, at the frequencies shown, and shall inspect all other occupied facilities on the installation quarterly. Pesticides shall not be applied in CYS facilities while children are present; only baits, traps and other low-risk methods approved by the IPMC may be used in CYS facilities.

5.5.3 Pest Service Calls. The Contractor shall respond to pest management DMOs within one business day. Stinging insects at CYS facilities, the Army Health Clinic or building entrances, and any rodent or bed bug sighting in food-service or CYS facilities shall be responded to within two hours during duty hours and four hours after duty hours. Historical service calls are shown in TE 10.

5.5.4 Rodent Control. The Contractor shall maintain and inspect monthly the exterior tamper-resistant rodent bait stations listed in TE 9, Table 9-2, and shall replace damaged or missing stations within five business days.

5.5.5 Vegetation and Turf Pest Control. The Contractor shall apply broadleaf weed control to improved grounds and athletic fields, pre-emergent crabgrass control to athletic fields, and vegetation control along fence lines and pavement edges at the frequencies in TE 9, Table 9-2. Applications shall not be made when wind speed exceeds 10 miles per hour or within 48 hours of forecast rain.

5.5.6 Mosquito and Tick Surveillance. The Contractor shall set and collect the surveillance traps in TE 9 weekly from 1 June through 30 September, ship specimens to the regional Army public health laboratory as directed by the IPMC, and apply larvicide to the stormwater areas in TE 9 when directed by the IPMC.

5.5.7 Exclusions. Pest management in family housing (RCI partner), fumigation, termite pre-construction treatment, and wildlife damage management requiring federal permits are excluded.

5.6 CLS 420 – FACILITY MAINTENANCE (DEMAND MAINTENANCE ORDERS)

5.6.1 General. The Contractor shall perform DMOs for minor maintenance and repair of real property on the installation, including carpentry, electrical, plumbing, heating and air conditioning, locksmith and painting work. A DMO requires not more than 16 labor hours and not more than $2,500 in material. Work exceeding these limits will be accomplished by the Government by other means unless the COR authorizes completion under this contract.

5.6.2 Priorities. Emergency (Priority 1) DMOs – conditions that endanger life, health, safety or security, or that will cause serious damage to property or mission – shall be responded to within one hour and made safe or completed within 24 hours. Urgent (Priority 2) DMOs shall be completed within five calendar days. Routine (Priority 3) DMOs shall be completed within 30 calendar days.

5.6.3 Estimated Workload. The estimated annual workload is 4,700 DMOs. CLIN 0006 is firm-fixed price for labor for up to 110 percent of the estimated quantity in each period; DMO material is reimbursed at cost without fee. Historical DMO data is shown in TE 10, Tables 10-2 and 10-3.

5.6.4 Work Management. The Contractor shall receive, schedule, document and close all DMOs in the Government's General Fund Enterprise Business System (GFEBS), recording labor hours, material and completion date for each order.

5.7 MEETINGS AND RECURRING REPORTS

5.7.1 Post-Award Conference. The Contractor shall attend a post-award conference within 15 calendar days after award.

5.7.2 Monthly Performance Review. The Project Manager shall meet with the Contracting Officer and COR monthly to review performance, and shall submit a Monthly Performance Report (CDRL A004) by the 5th business day of each month summarizing work completed for each CLS, quality control results, customer complaints and corrective actions.

PART 6 – APPLICABLE PUBLICATIONS

6.1 The Contractor shall comply with the following publications, current as of the date of the solicitation. Publications are available from the issuing agency's website or will be provided by the COR.

Publication	Title	Mandatory / Advisory	PWS Section
AR 420-1	Army Facilities Management	Mandatory	All
AR 200-1	Environmental Protection and Enhancement	Mandatory	1.15, 5.2, 5.5
AR 608-10	Child Development Services	Mandatory	1.11, 5.1
DA Pam 415-28	Guide to Army Real Property Category Codes	Advisory	TE 5
DA Pam 710-2-1	Using Unit Supply System (Manual Procedures)	Mandatory	3.1
DoDI 4150.07	DoD Pest Management Program	Mandatory	5.5
DoDI 1402.05	Background Checks on Individuals in DoD Child Care Services Programs	Mandatory	1.11
EM 385-1-1	USACE Safety and Health Requirements Manual	Mandatory	1.15
29 CFR 1910 / 1926	Occupational Safety and Health Standards / Construction	Mandatory	1.15
40 CFR 258	Criteria for Municipal Solid Waste Landfills	Mandatory	5.2
Wis. Adm. Code ch. ATCP 29	Pesticide Use and Control	Mandatory	5.5
Fort Brannock IPMP (FY26)	Integrated Pest Management Plan	Mandatory	5.5
Fort Brannock Snow Plan	Snow and Ice Removal Plan (FY27)	Mandatory	5.4
Brannock AAF BASH Plan	Bird/Wildlife Aircraft Strike Hazard Plan	Mandatory	5.3.3

PART 7 – ATTACHMENT / TECHNICAL EXHIBIT LISTING

7.1 The following Technical Exhibits are part of this PWS. The Contractor shall review the Technical Exhibits annually and recommend updates to the COR; approved updates will be incorporated by contract modification.

TE	Title	Pages
1	Performance Requirements Summary	1
2	Deliverables Schedule	1
3	Estimated Workload Summary	1
4	Custodial Cleaning Standards and Frequencies	1
5	Custodial Facility List – Part A, Facilities Serviced; Part B, Optional Facilities	2
6	Grounds Maintenance Areas	1
7	Refuse Collection Workload	1
8	Snow and Ice Removal Areas and Priorities	1
9	Pest Management Workload	1
10	Historical Workload Data	2
11	Installation Maps (electronic only)	—

TECHNICAL EXHIBIT 1 – PERFORMANCE REQUIREMENTS SUMMARY

Remedies are applied to the monthly invoice for the CLIN shown, in addition to re-performance at no cost to the Government.

No.	Performance Objective	PWS Para	Performance Standard	AQL	Method of Surveillance	Remedy
1	Custodial services performed in TE 5 Part A facilities	5.1	All tasks performed at TE 4 frequencies to TE 4 standards	95% of areas inspected acceptable	Random sampling, 10% of facilities per month	Re-perform within 4 hours; $150 per defective area above AQL (CLIN 0002)
2	Restroom dispensers stocked	5.1.4	No dispenser empty between services	98%	Random sampling; validated complaints	$50 per occurrence above AQL
3	Emergency cleaning response	5.1.10	Begin within 2 hours of notification	100%	100% inspection	$250 per occurrence
4	Refuse collected on schedule; no overflow	5.2	All lifts on scheduled day; area clean after lift	No more than 2 missed lifts per month	COR log; validated complaints	$75 per missed lift above AQL (CLIN 0003)
5	Improved grounds maintained	5.3.2	Turf 2½–4 in.; trimmed; clippings removed	90% of areas inspected	Periodic inspection, weekly in season	$200 per acre out of standard (CLIN 0004)
6	Priority 1 snow routes passable	5.4.3	Within 2 hours after start of operations	100%	100% inspection each event	$1,000 per occurrence (CLIN 0005)
7	Pest service calls answered	5.5.3	Within 1 business day (2 hours for urgent calls)	95%	GFEBS records	$100 per late call above AQL (CLIN 0007)
8	Emergency DMOs	5.6.2	Respond 1 hour; safe or complete 24 hours	100%	GFEBS records	$500 per occurrence (CLIN 0006)
9	Routine DMOs	5.6.2	Completed within 30 calendar days	92%	GFEBS records	$40 per late DMO above AQL
10	Deliverables	TE 2	Submitted complete and on time	100%	100% inspection	Recorded in CPARS

TECHNICAL EXHIBIT 2 – DELIVERABLES SCHEDULE

CDRL	Deliverable	PWS Para	Frequency / Due Date	Medium	Submit To
A001	Phase-In Plan	1.12	10 business days after award	Electronic	KO, COR
A002	Quality Control Plan	1.8	With proposal; updates within 10 business days of change	Electronic	KO, COR
A003	Key Personnel Resumes	1.10	With proposal; 10 business days before any change	Electronic	KO
A004	Monthly Performance Report	5.7.2	5th business day of each month	Electronic	COR
A005	Custodial Cleaning Schedule	5.1.3	With proposal; monthly by the 25th	Electronic	COR
A006	Pest Management Records (DD Form 1532-1) and Summary	5.5.1	Monthly, 5th business day	Electronic	IPMC, COR
A007	Refuse Tonnage Report with Scale Tickets	5.2.5	Monthly, 10th business day	Electronic	COR, DPW Environmental
A008	Snow Event Log	5.4.8	24 hours after end of each event	Electronic	COR
A009	Accident Report	1.15	Verbal 1 hour; written 5 business days	Electronic	COR, Safety Office
A010	ECMRA Labor Hour Report	1.13	Annually by 31 October	SAM.gov	—
A011	Key Control Inventory	1.11	Semiannually (January, July)	Electronic	COR

TECHNICAL EXHIBIT 3 – ESTIMATED WORKLOAD SUMMARY

Summary of the estimated annual workload by CLS. Quantities are taken from the detailed Technical Exhibits shown; where they differ, the detailed Technical Exhibit governs.

CLS	Workload Element	Estimated Quantity	Unit	Frequency / Annual Occurrence	Source
402 – CUSTODIAL SERVICES					
402	Facilities serviced (Part A)	47	EA	Per TE 5 frequency (7W to M)	TE 5
402	Cleanable area serviced (Part A)	557,560	CSF	Per TE 4 / TE 5	TE 5
402	Optional facilities (Part B) – not in base requirement	2	EA	40,160 CSF (design estimate)	TE 5
402	Special and emergency cleaning requests	55	EA	Per year (estimate)	TE 10
403 – REFUSE REMOVAL AND RECYCLING					
403	Front-load containers (4–8 CY)	43	EA	99 lifts per week	TE 7
403	Roll-off containers (20–40 CY)	4	EA	64 pulls per year	TE 7
403	Refuse and recyclables collected	1,844	TONS	Per year	TE 7
404 – MAINTENANCE – GROUNDS					
404	Improved grounds	83.1	AC	24 mowing cycles	TE 6
404	Semi-improved grounds	173.9	AC	4–8 mowing cycles	TE 6
404	Unimproved grounds	302.5	AC	1–2 cuttings	TE 6
404	Athletic fields	11.6	AC	48 mowing cycles	TE 6
404	Shrub and planting beds	58,400	SF	Weed 6 times; mulch 1 time	TE 6
404	Parking lots (policing and sweeping)	131,800	SY	Sweep 4 times	TE 6
404	Sidewalks and walkways	196,300	SF	Police weekly in season	TE 6
408 – SNOW, ICE AND SAND REMOVAL					
408	Roads and streets, Priorities 1–3	50.8	LM	14 events per season (fixed price)	TE 8
408	Parking areas cleared, Priorities 1–3 (part of TE 6 parking)	115,600	SY	Per event	TE 8
408	Sidewalks and entrances cleared (part of TE 6 sidewalks)	172,500	SF	Per event	TE 8
510 – PEST MANAGEMENT					
510	Scheduled structural services (Table 9-1 facilities)	17	BLDG	Monthly or quarterly	TE 9
510	Pest management service calls (DMO)	320	EA	Per year (estimate)	TE 10
420 – FACILITY MAINTENANCE					
420	Demand Maintenance Orders	4,700	EA	Per year (estimate)	TE 10

TECHNICAL EXHIBIT 4 – CUSTODIAL CLEANING STANDARDS AND FREQUENCIES

"Daily" tasks are performed on each service day of the facility (TE 5, column 13; PWS 2.1.9 and 2.1.10). Example: in a 3W facility, a "1X daily" task is performed three times per week.

Task	Capability I Enhanced	Capability II Standard	Capability III Basic
Restrooms, locker rooms and showers – clean and disinfect fixtures, partitions, floors	2X daily	2X daily	1X daily
Restock toilet tissue, towels, soap and seat covers	2X daily	2X daily	1X daily
Empty trash and recycling receptacles; replace liners	1X daily	1X daily	1X daily
Empty and disinfect diaper pails	2X daily	N/A	N/A
Sanitize cribs, cots, mats, toys, tables and chairs	1X daily	N/A	N/A
Sweep or dust-mop hard floors	1X daily	1X daily	1X daily
Damp-mop hard floors	1X daily	1X daily	1X weekly
Vacuum carpet – traffic lanes and open areas	1X daily	1X daily	1X daily
Vacuum carpet – edges, corners and under furniture	1X weekly	1X weekly	1X monthly
Spot-clean carpet	1X daily	1X weekly	1X monthly
Spray buff resilient floors	1X weekly	1X weekly	1X monthly
Strip and refinish resilient floors	2X yearly	2X yearly	1X yearly
Hot-water extract carpet	2X yearly	2X yearly	1X yearly
Clean entrance doors and glass	1X daily	1X daily	1X weekly
Clean interior glass and partitions	1X weekly	1X weekly	1X monthly
Clean exterior windows to 12 ft (both sides)	2X yearly	2X yearly	1X yearly
Dust horizontal surfaces below 7 ft	1X daily	1X weekly	1X weekly
High dust above 7 ft; vents and light fixtures	1X monthly	1X monthly	1X quarterly
Clean and sanitize drinking fountains	1X daily	1X daily	1X daily
Break rooms – counters, sinks, appliance exteriors, tables	1X daily	1X daily	1X daily
Disinfect fitness equipment contact surfaces and mats	N/A	1X daily	N/A
Dust-mop wood gymnasium floors	N/A	2X daily	N/A
Screen and recoat wood gymnasium floors	N/A	1X yearly	N/A
Clean saunas and steam rooms	N/A	1X daily	N/A
Flush floor drains	1X weekly	1X weekly	1X weekly
Wash walls, doors and frames (spot)	1X weekly	1X weekly	1X monthly

Standards. Floors: free of dust, dirt, litter, gum, stains, streaks and build-up; uniform gloss on finished floors. Restrooms: fixtures free of soil, scale, stains and odors; dispensers full and operable. Carpets: free of visible soil, litter and spots. Glass: free of smudges and streaks. Trash: receptacles empty, clean and lined. CYS facilities: surfaces sanitized with an EPA-registered sanitizer at the dilution required by the label and AR 608-10.

TECHNICAL EXHIBIT 5 – CUSTODIAL FACILITY LIST

Real property data as of 30 SEP 2026 (RPLANS / GFEBS). CSF verified by DPW Operations and Maintenance Division, OCT 2026. Frequency codes per PWS 2.1.9.

LINE	FAC NO	FACILITY DESCRIPTION	USING ORG	CATCD	YR BLT	FLRS	GSF[1]	CLEANABLE SQUARE FEET (CSF)[2]				FREQ	NOTES
								RESTROOM SF	CARPET SF	HARD FLOOR SF	TOTAL CSF		
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)	(11)	(12)	(13)	(14)
PART A – FACILITIES SERVICED (BASE REQUIREMENT, CLIN 0002 / x002)													
CAPABILITY I – ENHANCED SERVICE (CHILD, YOUTH AND SCHOOL SERVICES FACILITIES)													
1	3101	Child Development Center I	CYS	74028	2009	1	28,640	1,860	9,420	13,950	25,230	5W	3
2	3104	Child Development Center II	CYS	74028	2016	1	32,180	2,140	10,860	15,320	28,320	5W	3
3	3108	School Age Center	CYS	74029	2004	1	18,450	1,020	4,980	9,870	15,870	5W	
4	3110	Youth Center	CYS	74085	1998	1	21,760	1,310	3,240	14,050	18,600	6W	
5	3112	CYS Parent Central Services	CYS	61050	1987	1	4,820	210	3,060	980	4,250	5W	
	Capability I Total (5 Facilities)						**105,850**	**6,540**	**31,560**	**54,170**	**92,270**		
CAPABILITY II – STANDARD SERVICE (PHYSICAL FITNESS AND RECREATION FACILITIES)													
6	1520	Physical Fitness Center (Bergstrom)	DFMWR	74046	1992	2	46,300	4,860	1,120	31,640	37,620	7W	3, 10
7	1524	Physical Fitness Center (North)	DFMWR	74046	2012	1	38,900	3,920	760	28,450	33,130	7W	3, 10
8	1530	Indoor Pool	DFMWR	74054	1979	1	24,600	3,450	0	6,980	10,430	7W	11
9	1532	Outdoor Pool Bathhouse	DFMWR	74055	1968	1	2,940	1,180	0	1,240	2,420	7W	6
10	1540	Bowling Center	DFMWR	74012	1984	1	19,800	860	4,920	3,260	9,040	7W	7
11	1544	Outdoor Recreation Center	DFMWR	74056	1990	1	7,460	240	610	2,880	3,730	3W	
	Capability II Total (6 Facilities)						**140,000**	**14,510**	**7,410**	**74,450**	**96,370**		
CAPABILITY III – BASIC SERVICE (ADMINISTRATIVE, TRAINING, MAINTENANCE, WAREHOUSE AND OTHER FACILITIES)													
12	1001	Garrison Headquarters	GARRISON	61050	1941	3	52,880	2,460	26,350	9,870	38,680	5W	3
13	1002	DPW Administration	DPW	61050	1958	2	18,240	740	9,880	4,120	14,740	5W	
14	1004	Military Personnel Division / DHR	DHR	61050	1962	2	21,600	880	11,240	5,690	17,810	5W	
15	1006	Installation Transportation Office	LRC	61050	1965	1	9,350	420	3,980	3,640	8,040	5W	
16	1010	Main Post Chapel	RSO	73017	1943	1	11,420	520	5,860	2,460	8,840	2W	
17	1012	Religious Education Center	RSO	73018	1974	2	13,280	610	6,420	3,940	10,970	2W	
18	1020	Army Community Service	DFMWR	74016	1971	1	12,640	560	7,320	2,870	10,750	5W	
19	1022	Education Center	DHR	74021	1988	2	24,180	1,040	13,460	5,210	19,710	5W	
20	1024	Post Library	DFMWR	74034	1966	1	14,960	480	9,610	1,950	12,040	6W	
21	1026	Transition Assistance Center (SFL-TAP)	DHR	61050	1999	1	7,840	330	4,970	1,180	6,480	5W	
22	1030	Military Police Station	DES	73024	1976	2	16,720	760	4,980	8,630	14,370	7W	3
23	1032	Fire Station No. 1	DES	73016	1993	1	13,860	920	1,240	3,960	6,120	7W	8
24	1034	Visitor Control Center	DES	73075	2011	1	3,180	220	0	2,340	2,560	7W	
25	1040	Logistics Readiness Center Headquarters	LRC	61050	1981	2	17,960	720	9,140	3,860	13,720	5W	
26	1044	Network Enterprise Center	NEC	13115	1997	1	12,480	410	5,880	1,960	8,250	5W	
27	1050	Fort Brannock Museum	GARRISON	76010	1939	2	9,720	280	1,640	5,480	7,400	2W	
28	1402	UPH Barracks	GARRISON (UH)	72111	1987	3	46,800	2,380	0	6,940	9,320	5W	5
29	1403	UPH Barracks	GARRISON (UH)	72111	1987	3	46,800	2,380	0	6,940	9,320	5W	5
30	1404	UPH Barracks	GARRISON (UH)	72111	2006	4	61,240	2,960	0	8,720	11,680	5W	5
31	1405	Battalion Headquarters / Company Operations	TNG BN	14185	2006	2	28,450	1,140	10,980	9,460	21,580	5W	

LINE	FAC NO	FACILITY DESCRIPTION	USING ORG	CATCD	YR BLT	FLRS	GSF[1]	CLEANABLE SQUARE FEET (CSF)[2]				FREQ	NOTES
								RESTROOM SF	CARPET SF	HARD FLOOR SF	TOTAL CSF		
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)	(11)	(12)	(13)	(14)
32	1407	UPH Barracks – VACANT, NO SERVICE	VACANT	72111	1962	3	38,200	–	–	–	–	—	4
33	2104A	NCO Academy Classroom Building	NCOA	17120	1983	2	22,940	980	8,860	9,170	19,010	5W	
34	2104B	NCO Academy Classroom Annex	NCOA	17120	1983	1	9,860	420	3,640	4,380	8,440	5W	
35	2110	Simulation Training Center	DPTMS	17136	2014	1	26,780	760	14,120	3,980	18,860	3W	
36	2120	Range Control	DPTMS	14190	1995	2	8,640	380	3,120	3,410	6,910	5W	
37	2302	Tactical Equipment Maintenance Facility (TEMF)	TNG BN	21410	2009	2	64,300	1,620	1,860	4,240	7,720	5W	8
38	2306	Vehicle Maintenance Shop (Motor Pool B)	LRC	21410	1978	1	21,450	640	0	2,180	2,820	3W	8
39	2310	DPW Shops and Yard Office	DPW	21910	1964	1	33,600	560	980	2,140	3,680	3W	8
40	2402	Central Issue Facility	LRC	44220	1985	1	42,800	620	2,460	9,880	12,960	5W	
41	2404	General Purpose Warehouse	LRC	44220	1956	1	56,400	380	1,240	5,980	7,600	W	
42	2406	Self-Service Supply Center	LRC	44222	1972	1	6,720	160	0	4,840	5,000	2W	
43	2408	Records Holding Area	GARRISON	44224	1958	1	8,400	0	0	1,200	1,200	M	
44	2602	Airfield Operations Building	AAF	14112	1990	2	15,320	640	6,180	4,520	11,340	7W	
45	2604	Aircraft Maintenance Hangar	AAF	21110	1990	1	48,600	760	2,240	3,960	6,960	5W	8
46	2702	ASP Office and Break Facility	LRC	42210	1981	1	2,860	120	0	1,840	1,960	W	9
47	2812	Range 12 Control Tower and Classroom	DPTMS	17140	2005	2	1,840	160	0	1,260	1,420	W	
48	2818	Range 18 Ammunition Breakdown / Latrine Building	DPTMS	17140	2007	1	960	240	0	420	660	W	
	Capability III Total (36 Facilities)						**815,070**	**28,650**	**177,650**	**162,620**	**368,920**		
	TOTAL – PART A, ALL CAPABILITY LEVELS (excludes vacant Bldg 1407, Note 4) (47 Facilities)						**1,060,920**	**49,700**	**216,620**	**291,240**	**557,560**		
PART B – OPTIONAL FACILITIES (NOT IN BASE REQUIREMENT; OPTIONAL CLIN 0010 / x010, NOTE 12)													
B-1	1410	UPH Barracks (under construction)	GARRISON (UH)	72111	2028 est.	4	72,600	3,260	0	10,180	13,440	5W	5, 12
B-2	3116	Child Development Center III (programmed)	CYS	74028	2029 est.	1	30,400	2,040	10,120	14,560	26,720	5W	3, 12
	Total – Part B, Optional Facilities (2 Facilities)						**103,000**	**5,300**	**10,120**	**24,740**	**40,160**		

NOTES:

1. GSF (column 8) is the gross area recorded for the facility in the Army real property inventory (RPLANS / GFEBS) as of 30 SEP 2026. GSF is provided for information only and is not the basis for payment.
2. CSF (column 12) is the area to be serviced and is the basis for pricing CLIN 0002 / x002 and for workload adjustments under PWS 1.14. Column 12 = column 9 + column 10 + column 11. Mechanical, electrical and communications rooms, kitchens and food-preparation areas, vaults, attics, crawl spaces, and the areas excluded by Notes 5, 7, 8 and 11 are not included in CSF.
3. Restrooms (and locker rooms in Bldgs 1520 and 1524) are serviced 2X daily on each service day (TE 4).
4. Bldg 1407 was vacated 30 SEP 2026 and is programmed for demolition (FY28). It is listed for real property reference only. No custodial service is required; it is not included in any total in this exhibit.
5. UPH barracks: common areas only (entry lobbies, dayrooms, laundry rooms, corridors, stairwells and common latrines). Soldier living modules are excluded.
6. Seasonal operation, Memorial Day weekend through Labor Day (approximately 15 weeks), plus one opening clean and one closing clean. No service outside the season.
7. Bowling lanes, approaches, pinsetter area and the snack bar kitchen are maintained by the NAF activity and are not included in CSF.
8. Maintenance, shop, fire station and hangar facilities: offices, break rooms, latrines, locker / shower rooms, dayrooms and classrooms only. Work bays, apparatus bays, shop floors and hangar floors are excluded.
9. Escort required. Access shall be scheduled with the ASP supervisor not less than 24 hours in advance.
10. Hard floor SF includes the wood gymnasium floors (Bldg 1520: 14,200 SF; Bldg 1524: 11,600 SF). See PWS 5.1.9.
11. The pool basin and natatorium deck are maintained by NAF aquatics staff; CSF is lobby, offices, locker rooms and showers.
12. Part B facilities are not part of the base requirement and shall not be serviced until the Contracting Officer exercises Optional CLIN 0010 (x010 in option periods) by written modification after beneficial occupancy (PWS 5.1.12). GSF and CSF for Part B are design estimates.

Frequency codes (column 13) are defined in PWS 2.1.9: 7W, 6W, 5W, 3W, 2W, W and M.

TECHNICAL EXHIBIT 6 – GROUNDS MAINTENANCE AREAS

Mowing season 1 May – 15 October (24 weeks). Areas measured from DPW GIS, SEP 2026. See TE 11 for maps of each area.

Table 6-1. Grounds Areas by Type

Area ID	Area Description	Grounds Type	Quantity	Unit	Mowing Cycles (# Times Annually)	PWS Para
G-01	Cantonment core – Garrison HQ, chapel, community and administrative facilities (Bldgs 1001–1050)	Improved	21.6	AC	24	5.3.2
G-02	Barracks and battalion area (Bldgs 1402–1410)	Improved	17.3	AC	24	5.3.2
G-03	Child, Youth and School Services campus (Bldgs 3101–3116)	Improved	8.9	AC	24	5.3.2
G-04	Fitness and recreation complex (Bldgs 1520–1544), excluding athletic fields	Improved	12.4	AC	24	5.3.2
G-05	Main Gate and North Gate, Brannock Boulevard medians, road rights-of-way to 30 ft	Improved	19.8	AC	24	5.3.2
G-06	Post cemetery (hand trim at headstones)	Improved	3.1	AC	24	5.3.2
G-07	Industrial area, motor pools and DPW yard (Bldgs 2302–2416)	Semi-Improved	41.7	AC	8	5.3.3
G-08	Brannock AAF – airfield infield, clear zones and runway shoulders (BASH height, Note 3)	Semi-Improved	86.4	AC	6	5.3.3
G-09	Ammunition Supply Point – inside fence (Bldg 2702) (Note 4)	Semi-Improved	18.2	AC	8	5.3.3
G-10	Range complex – Range Control, Ranges 12 and 18, range road shoulders	Semi-Improved	27.6	AC	4	5.3.3
G-11	Firebreaks and perimeter fence lines	Unimproved	264.0	AC	1	5.3.4
G-12	Stormwater ponds, drainage channels and retention basins	Unimproved	38.5	AC	2	5.3.4
G-13	*Family housing areas (Residential Communities Initiative) – NOT IN CONTRACT (Note 5)*	*Improved*	*146.0*	*AC*	—	—
	Subtotal – Improved (G-01 through G-06)		**83.1**	**AC**		
	Subtotal – Semi-Improved (G-07 through G-10)		**173.9**	**AC**		
	Subtotal – Unimproved (G-11 and G-12)		**302.5**	**AC**		
	TOTAL – CONTRACT GROUNDS, TABLE 6-1 (excludes G-13)		**559.5**	**AC**		

Table 6-2. Athletic Fields

Field	Location	Quantity	Unit	Mowing (# Times Annually)	Lining (# Times Annually)
F-1	Softball Field 1 (east of Bldg 1524)	2.3	AC	48	34
F-2	Softball Field 2 (east of Bldg 1524)	2.3	AC	48	34
F-3	Brannock Stadium – football / soccer (natural turf)	2.9	AC	48	22
F-4	Multi-purpose / PT field (south of Bldg 1405)	4.1	AC	48	30
	TOTAL – ATHLETIC FIELDS (not included in Table 6-1)	**11.6**	**AC**		**120**

Table 6-3. Landscaped Beds and Paved Areas

Item	Description	Quantity	Unit	Estimated Workload (# Times Annually)	PWS Para
1	Shrub and planting beds (mulched)	58,400	SF	Weed 6; prune 1; mulch 1	5.3.6
2	Parking lots – policing and sweeping (Note 6)	131,800	SY	Police 38; sweep 4; spring sand removal 1	5.3.7
3	Sidewalks, walkways and building entrances – policing	196,300	SF	Police 38; blow after each mowing	5.3.7
4	Edging – walks and curbs adjacent to improved grounds (workload only; not an area)	54,600	LF	Edge 12	5.3.2

NOTES:

1. Quantities are horizontal (plan) areas. Building footprints, pavements and beds are excluded from turf acreage.
2. Grounds types are defined in PWS 2.1.11 through 2.1.13. Mowing cycles are the estimated number of complete mowings per year.
3. G-08: maintain 7–14 in. IAW the Brannock AAF BASH Plan; coordinate with Airfield Operations 24 hours in advance (PWS 5.3.3).
4. G-09: escort required inside the ASP fence; schedule with the ASP supervisor 24 hours in advance.
5. G-13 (146.0 AC) is maintained by the RCI partner and is listed for information only. It is not part of this contract and is not included in any subtotal or total.
6. Parking lots include the motor pool hardstands and ASP lots (16,200 SY) that are policed and swept under this contract but cleared of snow by the using units (TE 8, Note 1).
7. Fertilizer, herbicide and pre-emergent applications on grounds areas are listed in TE 9, Table 9-2, and are performed under CLS 510.

TECHNICAL EXHIBIT 7 – REFUSE COLLECTION WORKLOAD

Container inventory as of 30 SEP 2026. Building numbers identify the container location and the facilities served; they do not indicate custodial service (see TE 5).

Table 7-1. Front-Load Containers

No.	Location / Facilities Served	Bldg No(s).	Stream	Size (CY)	Qty	Pickups per Week	Lifts per Week
1	Garrison Headquarters	1001	MSW	6	2	2	4
2	Garrison Headquarters	1001	OCC	6	1	1	1
3	DPW / DHR / ITO administrative cluster	1002, 1004, 1006	MSW	6	2	2	4
4	Chapel / Religious Education Center	1010, 1012	MSW	4	1	1	1
5	ACS / Education Center / Library	1020, 1022, 1024	MSW	6	2	2	4
6	MP Station / Fire Station / VCC	1030, 1032, 1034	MSW	4	2	2	4
7	Army Health Clinic (MEDCOM) (Note 2)	1100	MSW	6	2	3	6
8	Dining Facility (Warrior Restaurant)	1310	MSW	8	2	6	12
9	Dining Facility (Warrior Restaurant)	1310	OCC	8	1	2	2
10	UPH Barracks	1402, 1403, 1404	MSW	8	4	3	12
11	UPH Barracks	1402, 1403, 1404	CMR	6	2	1	2
12	Battalion HQ / NCO Academy	1405, 2104A, 2104B	MSW	6	2	2	4
13	Fitness Centers / Indoor Pool	1520, 1524, 1530	MSW	6	2	2	4
14	Bowling Center / Brannock Club (NAF)	1540, 1550	MSW	8	2	3	6
15	Commissary (DeCA)	1600	MSW	8	2	3	6
16	Commissary (DeCA)	1600	OCC	8	2	2	4
17	TEMF / Motor Pool B	2302, 2306	MSW	8	3	2	6
18	DPW Shops / CIF / Warehouse	2310, 2402, 2404	MSW	8	2	1	2
19	Brannock AAF	2602, 2604	MSW	6	2	2	4
20	CYS campus	3101–3112	MSW	6	3	3	9
21	Range complex (Note 3)	2120, 2812, 2818	MSW	4	2	1	2
	TOTAL – FRONT-LOAD CONTAINERS				**43**		**99**

Table 7-2. Roll-Off Containers

No.	Location / Material	Bldg No.	Size (CY)	Qty	Estimated Pulls per Year
1	DPW yard – construction and demolition debris	2310	30	1	26
2	TEMF – scrap metal (non-hazardous)	2302	30	1	12
3	Range complex – range cleanup debris	2120	20	1	8
4	Self-Service Supply Center – bulky items	2406	40	1	18
	TOTAL – ROLL-OFF			**4**	**64**

Table 7-3. Estimated Annual Quantities

Waste Stream	Estimated Tons per Year
Municipal solid waste (MSW)	1,146
Old corrugated cardboard (OCC)	168
Commingled recyclables (CMR)	120
Construction and demolition (C&D) debris	410
TOTAL	**1,844**

NOTES: 1. MSW = municipal solid waste; OCC = old corrugated cardboard; CMR = commingled recyclables (paper, plastics 1–2, aluminum and steel cans). 2. Bldg 1100: regulated medical waste is removed by the MEDCOM contractor and is excluded (PWS 5.2.6). 3. Range complex containers are serviced 1 April – 30 November only; quantities shown are in-season. 4. Bldgs 1100, 1310, 1550 and 1600 are not serviced under CLS 402 (PWS 1.2.1, 5.1.13).

TECHNICAL EXHIBIT 8 – SNOW AND ICE REMOVAL AREAS AND PRIORITIES

Snow season 15 October – 30 April. Priorities and response times per PWS 5.4.3. Maps of each priority are in TE 11.

Table 8-1. Roads and Streets

Priority	Routes	Lane-Miles	Response
1	Brannock Boulevard (Main Gate to Brannock AAF); Hollister Avenue; access routes to the Army Health Clinic (1100), Military Police Station (1030), Fire Station No. 1 (1032), Visitor Control Center (1034) and Airfield Operations (2602)	16.4	Passable within 2 hours; maintained during event
2	CYS campus loop (3101–3112); barracks and battalion area (1402–1405); NCO Academy (2104A/B); Dining Facility (1310); fitness complex; motor pool access roads	22.8	By 0600 next duty day
3	All other paved installation roads, excluding family housing streets (RCI) and range roads	11.6	Within 24 hours after event
	TOTAL – ROADS AND STREETS	**50.8**	

Table 8-2. Parking Areas, Sidewalks and Entrances (areas are part of TE 6, Table 6-3)

Priority	Facilities Served	Parking (SY)	Sidewalks and Entrances (SF)
1	1001, 1030, 1032, 1034, 1100, 2602	21,600	38,200
2	1310, 1402–1405, 1520, 1524, 2104A, 2104B, 3101–3112	54,300	81,400
3	All other lots and walks listed in TE 6, Table 6-3, except Notes 1 and 2	39,700	52,900
	TOTAL CLEARED BY CONTRACTOR	**115,600**	**172,500**

Table 8-3. Snow Season Planning Data

Item	Quantity	Unit
Normal seasonal snowfall (30-year normal)	64	IN
Snow events of 2 inches or more included in CLIN 0005	14	EVENTS / SEASON
Estimated ice-control applications (included in CLIN 0005)	24	EA / SEASON
Government salt stockpile capacity (Facility 2416)	1,200	TONS

NOTES: 1. Motor pool hardstands and ASP lots (16,200 SY of the 131,800 SY in TE 6, Table 6-3) are cleared by the using units and are not included above. 2. Seasonal walks at the outdoor pool, outdoor recreation center and athletic fields (23,800 SF of the 196,300 SF in TE 6, Table 6-3) are not cleared. 3. Airfield pavements are cleared by the Government; the Contractor clears only the Airfield Operations parking lot and entrances.

TECHNICAL EXHIBIT 9 – PEST MANAGEMENT WORKLOAD

Facilities and areas are listed for pest management only. Listing in this exhibit does not indicate custodial service (see TE 5).

Table 9-1. Scheduled Structural Pest Management Services

Facility Group	Bldg Nos.	No. of Bldgs	Service	Frequency
Food service (Dining Facility, Commissary, Bowling Center snack bar, Brannock Club)	1310, 1600, 1540, 1550	4	Inspect / treat	Monthly
Child, Youth and School Services (low-risk methods only)	3101, 3104, 3108, 3110, 3112	5	Inspect / monitor	Monthly
Medical (Army Health Clinic, Veterinary Treatment Facility)	1100, 1106	2	Inspect / treat	Monthly
UPH barracks (including bed bug monitoring)	1402, 1403, 1404	3	Inspect / treat	Quarterly
Warehouses and CIF (stored product pests)	2402, 2404, 2406	3	Inspect / treat	Quarterly
TOTAL – SCHEDULED FACILITIES		**17**		
All other occupied facilities, installation-wide (estimated 2,846,300 SF of structural area; approx. 5% treated per year)	—	—	Inspect	Quarterly

Table 9-2. Vegetation, Turf and Outdoor Pest Management

Description	Quantity	Unit	Applications / Services (# Times Annually)
Broadleaf weed control – improved grounds and athletic fields (TE 6, Tables 6-1 and 6-2)	94.7	AC	2
Pre-emergent crabgrass control – athletic fields	11.6	AC	1
Turf fertilization – athletic fields and G-01, G-03	42.1	AC	3
Fence-line and pavement-edge vegetation control	41,800	LF	2
Mosquito larviciding – stormwater ponds (portion of TE 6, G-12)	22.0	AC	Up to 6
Mosquito and tick surveillance traps (1 June – 30 September)	12	EA	17 (weekly)
Exterior rodent bait stations	186	EA	12
Termite inspection – wood-frame facilities	38	BLDG	1

NOTE: Turf and vegetation quantities in Table 9-2 are treatment areas for CLS 510. They overlap the grounds areas in TE 6 and are not additional grounds to be maintained under CLS 404.

TECHNICAL EXHIBIT 10 – HISTORICAL WORKLOAD DATA

The workload data below is provided for historical purposes only. It does not represent a guarantee of future workload.

Table 10-1. Current Contract

Item	Information
Contract number	W9131B-22-C-0003
Contractor	Northwoods Integrated Services, LLC
Contract type	Firm-fixed price with cost-reimbursable DMO material line items
Date of award	27 June 2022
Period of performance	1 July 2022 – 30 June 2027 (12-month base period and four 12-month option periods; 60 months)
Total contract value, base period and all option periods (as awarded)	$38,947,260
Services included	CLS 402, 403, 404, 408 and 420. Pest management (CLS 510) was performed under a separate contract, W9131B-23-P-0118, and is consolidated into this requirement.

Table 10-2. Demand Maintenance Orders Received, by Priority

Priority	FY23	FY24	FY25
Emergency (Priority 1)	412	388	431
Urgent (Priority 2)	1,186	1,240	1,207
Routine (Priority 3)	2,964	3,102	3,058
TOTAL DMOs	**4,562**	**4,730**	**4,696**
Labor hours recorded	21,840	22,615	22,390

Table 10-3. Demand Maintenance Orders by Craft, FY25

Craft	DMOs	Labor Hours
Carpentry / structural	812	4,120
Electrical	954	4,385
Plumbing	1,106	5,210
Heating, ventilation and air conditioning	1,018	5,640
Locksmith	386	1,180
Painting	214	1,240
Other	206	615
TOTAL FY25	**4,696**	**22,390**

Table 10-4. Custodial Services

Item	FY23	FY24	FY25
Facilities serviced (30 September)	46	46	47
CSF serviced (30 September)	538,215	541,880	546,680
Special and emergency cleaning requests	52	47	58
Resilient floor area stripped and refinished (SF)	186,400	192,800	179,600
Carpet area extracted (SF)	238,400	244,100	249,800
Validated customer complaints	31	26	22

Table 10-5. Grounds Maintenance

Item	FY23	FY24	FY25
Special-event mowing and trimming (EA)	18	22	20
Trees removed by DMO (EA)	31	26	38
Storm debris clean-ups (EA)	3	1	4
Athletic field linings (EA)	114	126	119

Table 10-6. Refuse Removal and Recycling (tons)

Stream	FY23	FY24	FY25
Municipal solid waste	1,182	1,164	1,146
Recyclables (OCC and CMR)	266	279	288
Construction and demolition debris	452	398	410
TOTAL	**1,900**	**1,841**	**1,844**
Additional lifts requested (EA)	44	39	41

Table 10-7. Snow and Ice Removal

Item	2022–23	2023–24	2024–25
Seasonal snowfall (IN)	74	39	61
Snow events of 2 inches or more (EA)	18	9	15
Ice-control-only call-outs (EA)	9	14	8
Salt applied (TONS)	812	540	705
Sand applied (TONS)	1,380	860	1,240

Table 10-8. Pest Management

Item	FY23	FY24	FY25
Pest management service calls (DMO)	318	296	342
Scheduled structural services performed	150	156	156
Bed bug treatments (rooms)	14	9	11
Surveillance trap collections	198	204	204